Item NO	Descripiton	Unit	Estimted Quantity	Bid Unit Price	Bid Amount
1	MOBLIZATION DEMOBLIZATION	LS	1		
2	TEST PITS	CY	8		
3	EXCAVATION BELOW GRADE	CY	1231		
4	ROCK REMOVAL	CY			
5	6-INCH C900 PVC PIPE	LF	1460		
6	4-INCH C900 PVC PIPE	LF	10		
7	1-INCH POLYEHYLENE SERVICE TUBING	LF	655		
8	SERVICE LINE CONNECTIONS	EA	11		
9	6-INCH GATE VALVES AND BOXES	EA	4		
10	1-INCH AIR RELEASE VALVES	EA	1		
11	PAVEMENT RESTORATION	SY	209		
12	FLAGMEN/OFF-DUTY UNIFROMED POLICE OFFICE	HR	16		
13	8-INCH C900 PVC PIPE	LF	5		
			TOTAL OF ALL UNIT PRICE BASE BID ITEMS		

Excavation

Depth (ft)	Width (ft)	Length (ft)	Expansion	Volume (CF	Volume (CY)
4	3	2130	0.3	33228	1231

Pavement Restoration

Width (ft)	Length (ft)	Area (SF)	Area (SY)
3	627	1881	209